

PANHANDLE EASTERN PIPE LINE COMPANY

Jones 1-11
C SE NW
Section 11-35S-43W
Morton County, Kansas

Formation Tops

Marmaton	3820'
Cherokee	3885'
Atokan	4067'
Morrowan Shale	4184'
"G" Ss.	4557'
Keyes Ss.	4598'
Mississippian	4634'
Total Depth	4712'

Completion Information

Spud April 18, 1955.
Set 320' of 13 3/8" casing with 250 sacks cement.
Set 1331' of 8 5/8" casing with 225 sacks cement.
Set 4619' of 5 1/2" casing with 400 sacks cement.
Cleaned out to 4575'.
Perforated 56 holes 4558-4572'.
Acidized with 250 gallons mud acid.
Fractured with 1500 gallons and 500# sand.
Fractured with 2000 gallons.

Completion Test: July 26, 1955.
Calculated open flow 1775 MCF
from Morrowan "G" Ss. 4558-4572'.
Dual completion with the
Greenwood Reservoir.