

2-217W MAP NO. 82 ✓

SEC. 6-35S-43W

STATE Kans COUNTY Morton

LOC C SE NE

OPER. Oil & Gas Futures Inc.

FT/FR LINE

WELL 1 FARM U.S. Government

FT/FR LINE

L Interstate Ext

ELEV.

GR. 3556

DF 3559

KB

CONT. Service Drlg., Co.

GEOL.

CO.

INT.

F.R. 11-30-62 PUD 12-3-62 COMP. 2-26-63


TD 4533 FM. Keyes

PBTD.

8 5/8" @1250/650 sx. - 5 1/2" @4403/110 sx.

Morr 4201- Notch - Jet 150A

Co P 36 BOPD + 7% wtr (No Gravity available)



Data Inc.

-COMP
RECORD

(KB Log Tops)

Waub	2558	+1001	Morr	4115	- 556
Top	2756	+ 803	Morr sd	4194-4216	- 635
Grnwood-Lans	2998	+ 561	Sand	4227	- 668
Lans	3174	+ 385	Keyes	4599	- 950
Marm	3651	- 92	LTD	NA	
Chero	3841	- 282	RTD	4533	- 974

☛ #1 (Purdy) 4189-4216, R 21' sd, coarse grw/stain + 3 1/2' sh + 1/2' shly sd

DST #1 (Purdy) 4195-4216, Op 1 hr, GTS/5", TSTM, R 480' GCO + 120' O & GCM + 420' SW, IBHP 725#/35", IFP 120#, FFP 370# FBHP 735#/40", RTD 4533, Log, 5 1/2" 4403/110, Notch 4201 (Morr) 150A, (7 1/2%) § 1d, § 57 1/2 BO + 15 BSW/20 hrs, POP, P 36 BOPD, Cut 27% Wtr, Co P 36 BOPD + 7% wtr, Morr Jet 4201 COMPLETED (2-19-63)

LIBERAL LOG TOPS

3559 KB

Topeka 2754 (+805)

Heebner 3060 (+499)

Lansing 3170 (+389)

Morrow 4082 (-523)

"S-2" 4184 (-635) 21/22; ϕ P 36 BOPD + 7% Wtr

"S-2" 4230 (-671) 11/12; NT (?Wet)

Keyes 4507 (-948) 16' T

TD 4530