

5-180W+

MAP NO.

SEC. 8

TWP.

35S

RGE. 43W

STATE Kans. COUNTY Morton

LOC App S/2 NW SW

OPERATOR Anadarko Prod. Co.

660

FT. FROM west

LINE

WELL NO. 1

FARM NAME

Change chance

1800

FT. FROM south

LINE

Elkhart West

ELEV. 3601

GR

3605

DF

3607

E KB

FR. 3/14/62


SPUD 3/13/62

COMP. 5/15/62

CONT. Wakefield Drlg. Tools

/GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
Morr	4232½	5 way jet	2000A&Frac
b			
c			
d			



Go P

d I. P. OIL/DIST. 70 BO

WTR. 30 BW

GAS

M.C.F.P.D.

CHK.

HRS.

24

b

c

d

D & A ()

SIP#

FI TP #

FI CP#

SIBHP

GOR.

GR.

PSTD

4254

TD

4636

SIZE

DEPTH

CASING - CEMENT RECORD

SIZE

DEPTH

W/SAX.

8-5/8"

1287

600

4½"

4284

125

OPERATOR Anadarko Prod. Co.

WELL NO. 1

Change chance

ELEV. 3601 GL

SAMPLE TOPS

DEPTH

SUB SEA

ELEC. TOPS

DEPTH

SUB SEA

GL Tops & Datums

Red Cave 1294

RTD (Miss) 4636 -1035

DST #1 (RC) 1287-1360,

Op 92", GTS/3", Ga 77

Mcfgcd to 70 Mcfgcd/72",

R 575' wtry mud, Clor

3,600 PPM to 43,000 PPM,

IBHP 323#/30", IFP 50#,

FFP 301#, FBHP 334#/30"

DST #2 (Morr sd) 4228-70,

Op 1 hr., GTS/3", Ga 124

Mcfgcd/15", died, R 1200

Gasy Oil + 235' Oil + 800

SW, IBHP 988#/30", IFP 584-988#, FBHP 988#/30"

RTD 4636, Log, 4½" @4284 w/125 sx, MICT & CO 4254, 5 way

jet 4232 (Morr) \$ 20 GOPH/3 hrs, 500A, \$ 3 BOPH/NT, 16/4223

-27 (Morr) 1000A, \$ 12 GOPH/NW, \$ 24 GOPH/16 hrs, Sq all

B/Cimm

1295

+2306

Red Cave

1308-30

+2293

Admire

2452

+1149

Waub

2611

+ 990

Top

2794

+ 807

Greenwood Lans 3028

+573

Lans

3217

+ 384

Marm

3691

- 90

Chero

3884

- 283

Morr

4154

- 553

Up sd

4220-42

-619

Keyes sd

4544-4628

-943

Miss

4640

-1039

LTD

not available

perfs 75 sx, CO 4254 PBTD, 5 way jet 4232 $\frac{1}{2}$ (Morr), A/500
swb 11 BO/9 hrs, swb 1 $\frac{1}{2}$ BOPH/13 hrs, frac 5000 oil x 5000#
sd, swb ld, swb 55 BO/NT, kill well, 2" tbg 4242, swb ld,
swb 215 BO + 83 BW/16 $\frac{1}{2}$ hrs, POP, P 100 BO + 30% wtr/24 hrs,
P 70 BO + 30% wtr/24 hrs, Co. P 70 BO + 30 BW/24 hrs,
Morr 4232 $\frac{1}{2}$. COMPLETE.

LIBERAL ELECTRIC LOG TOPS

3608 KB

Topeka 2794 (+807)

Greenwood/Lansing 3028 (+573)

Lansing 3216 (+385)

Morrow 4114 (-513)

"S₂" Sand 4220 (-619) 15/20; ϕ Pmp 70 BO + 30 BW/24 hrs.

Keyes 4544 (-943) 46/82

Chester 4628 (-1027)

TD 4636