


90207

4-227W MAP NO. 82 ✓ SEC. 5-35S-43W
 STATE Kans COUNTY Morton LOC. C NW NW
 OPER. Anadarko Prod. Co. - Liberal, Kansas FT/FR _____ LINE _____
 WELL #2 FARM Webster "C" FT/FR _____ LINE _____
 COL Interstate ELEV. 3547 GR. 3550 (E) DF 3552 (E) KB _____
 CO. Graham-Michaelis Tools GEOL. _____
 INT. 4250' Oil Tst.
 F.R. 9/18/62 SPUD 10/20/62 COMP. 4/16/63
 TD. 4567 FM. Mississippian PBD. _____
 COMP. RECORD 8 5/8" @ 1232' w/600 sx. 4 1/2" @ 4320' w/100 sx.
TEMPORARY ABANDONED



(Gr) Log Elev. 3547 Gr.

Data Inc.

Top	2749 + 798	Keyes	4484-4500	- 937
Morr	4093 - 546	Miss	4500	- 953
U/Morr sd	4167-92 - 620	LTD	4567	-1020
Morr G sd	4438-4508 - 891	RTD	4565	-1018

DST #1 (Up Morr) 4060-4210', Op 60", GTS/2", Ga 1450 Mcfgpd/5", Ga 2530 Mcfgpd/10", Ga 2800 Mcfgpd/15", Ga 3120 Mcfgpd/25", Ga 3200 Mcfgpd/40", Ga 3310 Mcfgpd/60". No Rec or Press's on
 DST #1. SIP 735-735/30 FP 450-490

DST #2 (Morr-Keyes) 4404-4565', Op 1 hr, GTS/50", TSTM, Rec 155"
 GCM, IBHP 890#/30", IFP 102#, FFP 102#, FBHP 909#/30",

RTD 4565, Log, 4 1/2" @ 4320' w/100 sx. CO 4268, Perf 16/4184-88 (Morr), 250 A (7 1/2%), Flow 1/4 BOPH/3 hrs, Ga 1,2000 Mcfgpd, SIP 450#/1 hr, 7 1/2 hrs BD- 2,530 Mcfgpd, R 5 1/2 BO/3 hrs, R 2 BO/2 1/2 hrs, SEPR Press 200#, SD, Temporary Abandoned.

COMPLETED (4/9/63)

CORRECTION: (10/29/62) Was #1 Webster "C"; Is #2 Webster "C".

LIBERAL ELECTRIC LOG TOPS

3557 KB

Topeka 2748 (+809)

Heebner 3042 (+515)

Lansing 3154 (+403)

Morrow 4060 (-503)

"S-2" Sand 4168 (-611)22/24, g 2530 MCF + 7 B0/7½ hrs.

"S-3" Sand 4436 (-779)8/20 /tst gas TSTM

Keyes 4482 (-925)3/18

TD 4565

Temporarily Abandoned.