


1-365W
 MAP NO. _____ REPLACEMENT COMPLETION SEC. 5 TWP. 35S RGE. 21W
 STATE Kans COUNTY Clark LOC. C SW NE
 OPERATOR Graham Michaelis Drlg. Co. FT. FROM _____ LINE
 WELL NO. 1-5 FARM NAME Tuttle FT. FROM _____ LINE
 POOL Snake Creek ELEV. 1837 GR. 1845 DF. 1847 KB
 R. 1/25/62 SPUD 1/31/62 COMP. 4/3/62
 CONT. Co. tools /GEOL. _____

NAME PRODUCING INTERVAL COMPLETION RECORD
 FROM - TO PERF. W/HOLES TREATMENT RECORD
 Morrow 5532-66 112 1000A & Frac



Cal OF
 I. P. OIL/DIST. WTR. GAS 19,164 M.C.F.P.D. CHK. HRS. 24
 " " " " " "
 " " " " " "

SIP# 1425# FI TP # FI CP# SIBHP
 GOR. GR. PBTD 5600 TD 5656
 CASING - CEMENT RECORD
 SIZE 8 5/8" DEPTH 684 W/SAX. 400 SIZE DEPTH W/SAX.
 5 1/2" @ 5655

OPERATOR Graham Michaelis WELL NO. #1-5 Tuttle ELEV. 1847 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Kb Tops & Datums			Lans	4499	-2652
			Marm	5184	-3337
Lans	4497	-2704	Morr	5480	-3633
RTD (Miss)	5656	-3863	Morr sd	5531	-3684
			Morrow Sd	5545-85	-3698
			Miss	5598	-3751
			LTD (Miss)	Not Avail.	
DST #1 (Morr) 5478-5570, op 1 hr, GTS/2", Ga 3633 Mcfgpd					
45", & Stab, R 110' GCM, IBHP 1572#/30", IFP 1024#.					
FFP 1024#, FBHP 1599#/30".					
RTD 5656. Log. 5 1/2" @ 5655. CO 5600 PBTD, 40/5532-42					
72/5548-66 (Morr)Ga 2800 Mcfgpd, Nat 1000 A + Frac					
(20,000# sd x 20,000 GA), R 1d, Northern Nat 4 pt 1st					
Cal OF 19,164 Mcfgpd, SIP 1425# Morr 5532-66.					
NOTE: This test drilled tight by operator.					
REPLACEMENT COMPLETION Correct elev (was 1793 KB					
CORRECTION: (4-24-62) 1791 DF - 1783 Gr. Is 1847 KB					
Add'l log top - Lans. 1845 DF, 1837 Gr.)					