

MAP NO. _____ ELEV. 1882 GI
 STATE Kansas COUNTY Clark SEC. 6 Twp 35 S Rge 21 W
 OPERATOR Sinclair Oil & Gas Company LOC. C NW SE
 WELL NO. 1 FARM NAME C. H. Tuttle FT. FROM _____ LINE _____
 POOL Wildcat (PD 7600) FT. FROM _____ LINE _____
 FR. 7-10-61 SPUD. 7-14-61 COMP. 9-10-61

CONT./GEOL. Barbour Drilling Company

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
 a. Morrow 5590-5606 64 500A-F/20x20

b. _____

c. _____

d. _____

d I. P. OIL/DIST. _____ WTR. _____ GAS 8,500 M.C.F.P.D. _____ CHK. 3/4" HRS. _____

b. " " " " " "

c. " " " " " "

d. _____

SIP# _____ FI TP # 600 FI CP# 1300 SIBHP _____
 GOR. _____ GR. _____ PBD TD 7601

CASING - CEMENT RECORD

SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>30"</u>	<u>25</u>	<u>55</u>	<u>9-5/8"</u>	<u>2886</u>	<u>200</u>
<u>13-3/8"</u>	<u>606</u>	<u>600</u>	<u>4 1/2"</u>	<u>5695</u>	<u>400</u>

OPERATOR Sinclair O & G WELL NO. 1 C H Tuttle ELEV. 1892 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Elgin	4198		Topeka	3406	
Heebner	4338		Elgin Sand	4277	
Toronto	4386		Heebner	4367	
Lansing	4550		Lovell Sand	4406	
Marmaton	5198		Toronto	4428	
Cherokee	5328		Lansing	4552	
Morrow	5490		Marmaton	5240	
Chester	5562		Cherokee	5381	
1st Chester Sand	5591-5608		Morrow	5540	
2nd Chester Sand	5617-35		Lower Morrow Sand	5592	T +
Ste Genevieve	5795		Mississippian	5605	T +
St Louis	5840		Ste Genevieve	5786	T
Spergen	6042		St Louis	5845	
Warsaw	6308		Spergen	6034	
Osage	6537		Warsaw	6304	
Kinderhook	6840		Osage	6538	
Viola	7115		Kinderhook	6836	
Simpson Sand	7366-88		Viola	7117	T
			Simpson	7370	T
			Arbuckle	7480	T

SHEET NO. 2

MAP NO. _____

STATE Kansas COUNTY Clark SEC. 8 Twp 35 S Rge 21 WOPERATOR Sinclair Oil & Gas LOC. C NW SEWELL NO. 1 FARM NAME C. H. Tuttle

Spud 7-14-61. 30" @ 25 w/55 sx. 13 3/8" @ 606 w/600 sx. 9 5/8" 2886 w/200 sx.

DST #1 (Chester Sand) 5594-5611, op 1 hr, GTS 2 1/2 mins, Ga 2200 MCF/5 hrs, Ga 2400 MCF/10 mins, Ga 2500 MCF/15 mins. Ga 2600 MCF/60 mins, Rc 30' dist + 15' DCM, ISIP fld, FP 435-505, FSIP 1969/60 mins.

DST #2 (Chester Sand) 5620-50, op 1 hr, wk blo/died/3 mins, Rc 5' mud, ISIP 89/60 mins, FP 30-30, FSIP 30/60 mins.

DST #3 (Ste Genevieve) 5798-5834, op 1 hr, very weak blo/5 mins/died. Rc 15' mud, ISIP 125/60 mins, FP 38-38, FSIP 49/60 mins.

DST #4 (Simpson) 7366-7425, op 1 hr, GB dec to fr, Rc 360' MCSW + 2610 SW, ISIP 2942/60 mins, FP 416-1542, FSIP 2929/60 mins.

TD 7600, logs to 7601.

DST #5 (Arbuckle) 7508-7600, op 1 hr, fr blo/1 hr, Rc 360'

OPERATOR Sinclair Oil & GasWELL NO. #1 C. H. Tuttle

MCSW + 1265 SW, ISIP 3007/60 mins, FP 233-822, FSIP 2785/60 mins.

4 1/2" @ 5695 w/400 sx. MICT.

P/64/5590-5606, 500 MA, Flod pt 1d w/460 MCF. TP 50, CP 150, Frac 20,000 Ac X 20,000 sd. Flod 6 BLWPH w/6000 MCF, 3/4" ck, TP 1000, CP 12,000. Swb 168 BLW + 3 BC (Gty 56°)/NT.

IP 8500 MCF. 3/4" ck, FFP 600, FGP 1300 (no SIP), from Morrow (5590-5606).

COMPLETE 9-10-61.