

11-297W MAP NO. _____ REPL. COMP. SEC 9-35S-21W
 STATE Kans COUNTY Clark LOC C NE SE
 OPER Graham Michaelis Drlg. - Wichita, Kansas FT/FR _____ LINE
 WELL 1-9 FARM Tuttle FT/FR _____ LINE
 POOL Tuttle West ELEV 1909 GR 1916 DF 1919 KB
 CONT Co. tools GEOL. _____
 CO. 5750' Gas Test
 INT. 10-4-63 SPUD 10-4-63 COMP 11-26-63
 F.R. 5734 FM Chester PBTD Est 5700
 TD

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
	Morr	5642-82	92	1000A & Frac	
I.P. COF 8,000,000 Cfgpd (SIP 1337#)					

Casing Record	8 5/8" @660 w/500 sx.	4 1/2" @5730 w/125 sx.

Data Inc.

(KB Log)

Lans	4628	-2709	Chest	5696	-3777
Mrw sh	5590	-3671	LTD	NA	
" sd	5642	-3723	RTD	5734	-3815

DST #1 (Mrw) 5624-76, Op 90", GTS/10", Stab @324,000 Cfgpd,
 R 100' HGCM, ISIP 1388#/30", IFP 44#, FFP 88#, FSIP

1388#/30", RTD 5734 (Chest), Log, 4 1/2" @5730 w/125 sx.,
 Perf Mrw 48/5642-54 & 44/5671-82, show gas nat, 1000A, Ga
 279,000 Cfgpd, Frac 15,000# sd x 15,000 gal flu, Cal OF
 8,000,000 Cfgpd, SIP 1337#, Mrw 5642-82 - COMPLETED
 REPLACEMENT COMPLETION (12-24-63)
 CORRECTION - Corr Chester top - Was 4595 - Is 5696