


DAVIS & CHILD
Beyerlein No. 1.

SEC.17 T.3 R.18 W
CSW NE

Total Depth. 3656' DFM
Comm. 12-24-42 Comp. 1-11-43
Shot or Treated.
Contractor. H.M. Williams Drlg. Co.
Issued. 1-30-43

County. Phillips



CASING:
10" 155' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

soil	9
sand & shale	190
shale	450
shale & shells	929
sand & shells	965
shale & shells	1195
sand	1275
lime	1295
lime & sand	1530
lime	1555
red bed, shale & shells	1675
shale & shells	2160
lime & shale	2513
lime, shale, pyrites	2550 ✓
lime & shale	2772
shale sdy	2808
shale & shells	2920
sand & shells	2944
lime sdy	2980
lime	3034
lime wh sft	3038
lime cherty	3070
lime wh sft	3080
lime cherty	3176
shale blk	3179
lime cherty	3215
shale red	3217
lime cryst & shale red	3253
lime	3282
lime cherty & shale red	3352
lime cherty hd	3359
lime cherty	3390
lime w/shale rod & green	3424
shale	3440
lime gy nodular	3455
lime pink, yellow, & gy nodular	3480
shale red	3495
lime gy non-porous oclitic	3510
shale red, purple & green	3525
lime gy & nodular	3545
lime, dolomite red & green shale	3584
conglomerate	3602

lime Arbuckle 3656
Total Depth, Derr. Fl. Meas.

Tops:
Topeka 2978
Lansing-Kansas City 3217
slight oil stains 3217-18
slight oil stains 3253-54
Marmaton 3424
Conglomerate 3584
Arbuckle 3602

El. Top 3570
El. Log 3615