

22-3-18W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - COOPERATIVE REFINERY ASSOCIATION
Farm - Phillipsburg Ref. No. 1

SEC. 22 T. 3 R. 18W
QNL SE SE
1220' N of SL, & 660'
W of EL of SE/4.

Total Depth. 1178'

Comm. 9-4-47


Comp. 10-19-47

Shot or Treated.

Contractor. Russell Drilling Company

Issued. 1-10-48

County. Phillips
KANSAS



CASING:
12 1/2" 81' 7" 1110' cem. 925 sx.
10" 220'
8 5/8" 777' cem. 15 sx.

Elevation. _____

Production. S.W.D.W.

Figures Indicate Bottom of Formations.

soil	10
shale, grey	30
yellow clay	40
sand, fine	50
shale, blue	65
sand & gravel, coarse	80 HFT
shale, yellow	115
shale, dark	125
shale, brown	160
shale & sand	200
shale, blue	220
shale, brown	260
shale, light	300
shale, blue	685
lime	690
sand	695
shale, grey	725
shale, red	730
shale, grey	785
shale, red	810
shale, blue	865
sand	884
shale, red	905
sand	915
Iron & sand, sharp	925 ✓
sand	955
shale, blue	990
sandy shale	1000
shale, blue	1020
sand, white	1030
shale, blue	1046
sand, white-hard	1070
shale, green	1077
sand, white-hard	1080
shale, blue	1085
shale, green	1094
sand, soft	1109
sand, hard	1112
sand, soft	1120
shale, green	1121
sand, white-soft	1178
Total Depth.	