


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PHILLIPS CHEMICAL COMPANY  
Farm- Chem-Bohl No. 1

SEC. 13 T. 3 R.19W  
SW NW NW

Total Depth. 3390 P.B. 3362  
Comm. 11-18-51 Comp. 1-21-52  
Shot or Treated.  
Contractor.  
Issued. 2-23-52

County Phillips  
KANSAS



CASING:  
8" 290' cem. w/250 sx.  
5" 3390 cem. w/150 sx.

Elevation. 2018 D.F.

Production. I.P. Phys. pot.  
90 bbls. / 22 wtr.

Figures Indicate Bottom of Formations.

surface soil	10
lime brkn	60
shale	245
shale, shells	300
shale blue & shells	570
shale, sand	945
sand, redrock	1095
sand, shells & shale	1485
anhyd.	1535
redbed, shale	1750
shale, shells	1850
shale, lime stks	1990
shale, shells	2095
lime & shale	2160
lime	2216
lime & shale	2580
lime	2630
lime & shale	2765
lime	2800
lime & shale	3056
lime	3390
Total Depth P.B. 3362	

Tops:	
Silt	2898
Howard	2911
Topeka	2938
Base Silt	3026
Hubner	3109
Toronto	3134
Lansing-K.C.	3153
Base L-K-C.	3376

P.B. T.D. 3365, Perf. 32 shots 3320-28  
Acid 500 & 2000 gals. Swb. 2 B. & 7 gl.  
oil/2 hrs. Set Lane Wells Plug 3300  
Perf. 16 / 3246-3250, acid 500, Swb.  
1 1/4 BO & 1 1/2 BW in 2 hrs. P.B. 3356,  
Perf. 24 shots 3302-08, no incr. in  
fluid, Acid 1000 Bailed 2 1/2 BO & 1/4 BW  
in 5 hrs. Perf. 3183-90, acid 3000 gals.  
swb. 45 BO in 12 hrs, Set Lane-well plug 3170  
Perf. 40 / 3154 to 64 & 24 / 3135-41 acid  
w/3000 gals. Drove bridging plug to P.B. total  
depth 3362.