

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


14-3-19W

Company- PHILLIPS PETROLEUM CO.
Farm- Hempler No. 1

SEC. 14 T. 3 R. 19W
SW SE SE

Total Depth. 3340 P.B. 3307
Comm. 3-15-52 Comp. 4-18-52
Shot or Treated.
Contractor.
issued. 5-10-52

County Phillips
KANSAS



Elevation. 1963 D.F.

Production. I.P. 111 bbls.
12 wtr.

CASING:

8" 259 cem. w/250 sx.
5" 3329 cem. w/150 sx.

Figures indicate Bottom of Formations.

shale & lime	140
clay & shale	260
sticky blue clay	395
shale	985
sand	1173
shale, red bed, sand	1390
red bed	1450
Anhyd.	1485
shale & shells	1625
shale & shells	2030
lime & shale	2145
lime	2210
lime & shale	2605
shale	2735
shale & lime	3103
lime	3340
Total Depth	P.B. 3307

Tops:	
Howard	2845
Topeka	2873
Heebner	3041
Toronto	3065
Lansing-K.C.	3083
Base L.K.C.	3304
Marmaton	3323
Base Marmaton	3340

The following zones are perf. & open
3083-90; 3116-3124; 3135-3142; 3160-65
3208-16; 3233-40; 3250-57; 3274-3283