

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

508 East Murdock

Wichita, Kansas


12-3-23W

Company • GREAT LAKES CARBON CORP.
 Farm • Muir No. 1

SEC. 12 T. 3 R. 23W
 NW NW SW

Total Depth. 3722
 Comm. 6-27-51 Comp. 7-11-51
 Shot or Treated.
 Contractor. Honaker Drlg. Co. Inc.
 Issued. 8-4-51

County. Norton
 KANSAS



CASING:

8 5/8" 218' cem. w/150 sx

Elevation. 2341
 2344 RB (2nd)

Production. Dry

Figures Indicate Bottom of Formations.

top soil & clay	70
sand	105
shale	218
shale & clay	580
shale	680
sand & shale	1495
shale, sand, shells	1845
shale & shells	1930
anhydrite	1965
shale & lime	2030
red bed	2100
red bed & shale	2295
shale & shells	2600
lime & shale	2780
lime	2830
lime & shale	3692
lime	3704
lime & shale	3722
Total Depth	

Tops:

Anhydrite	1926
Heebner	3408
Toronto	3428
Lansing	3450
Sandy Conglomerate	3680
Arbuckle	3686
Granite Wash	3694
Granite	3705

Small show of oil 3433-37'
 Small show of oil 3610-12'
 Small show of oil 3686-94
 DST: 3687-92 open 1½ hrs.
 W.B. Rec. 150' mud & SW 15"
 BHP 790#.