

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-3-23W

Company- BURCH DRILLING CO., INC.
Farm- Horesky No. 1

SEC. 15 T. 3 R. 23W
SE SE NW

Total Depth. 3698'
Comm. 11-11-59 Comp. 11-19-59
Shot or Treated.
Contractor.
Issued. 1-23-60

County Norton
KANSAS



Elevation. 2386' KB

Production. Dry

CASING:

8 5/8" 219' cem w/165 sx.
5 1/2" 3689' cem w/75 sx.

Figures indicate Bottom of Formations.

shale & shells	960
shale	1967
Anhydrite	1992
shale	2390
lime & shale	3370
lime	3695 RTD
lime	3698
Total Depth	

TOPS:

Anhydrite	1968
Heebner	3426
Toronto	3452
Lansing	3466
Base Kansas City	3650
Arbuckle	3688

DST #1 3436-3543', op 1 hr., rec. 45'
mud, IBHP 1120#, IFP & FFP 0#, FBHP
1000#/30 min.

DST #2 3538-3654', op 1 hr., rec. 1080'
slightly oil cut watery mud. IBHP 1150#/30 mins.
IFP 105#, FFP 600#, FBHP 895#/30 mins.

DST #3 3680-3690', op 2 hrs. rec. 15'
oil, 60' muddy oil. IBHP 955#/30 min.
IFP & FFP 0#, FBHP 710#.

DST #4 3680-3695', op 2 hrs., rec. 15'
oil, 60' muddy oil. IBHP 725#/30 min.
IFP & FFP 0#, FBHP 510#/30 min.