

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

30-3-23W

Company- D.G. HANSEN
Farm- Weber

No. 2

SEC. 30 T. 3
NW NW SW

R. 23W

Total Depth. 3671'

Comm. 2-15-54


Shot or Treated.

Contractor.

Issued. 6-12-54

Comp. 2-23-54

County Norton
KANSAS



Elevation. 2353 R.B.

Production. 190 BO/no wtr

Figures indicate Bottom of Formations.

CASING:

8 5/8" 264'
5 1/2" 3693.22'

shale	510
shale-sand	925
shale	990
sand	1030
shale-sand	1195
sand	1225
shale-sand	1590
sand	1700
red bed	1940
Anhydrite	1980
shale-shells	2490
shale	2725
limo-shale	3671
Total Depth	

TOPS:

Dakota	887
Hoebner	3306
Toronto	3411
Iansing	3427
Base Kansas City	3610
Reagan	3668

#1 DST 838-925. Open 50 min.
Recovered 340 muddy salt wtr.,
w/135# BHP & FFP.

#2 DST 838-1225. Open 15 min.
Recovered 263 muddy wtr w/170#
BHP, 150# FFP, & 135# IFP.

#3 3437-66. Open 1/2 hr. Recovered
18' mud w/230# BHP.

Producing from Reagan Sand.