

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

30-3-23W

Company- D.G. HANSEN
Farm- Weber

No. 4

SEC. 30 T. 3
SE SE SW

R23W

Total Depth. 3741'

Comm. 3-3-54

Comp. 3-11-54


Shot or Treated.

Contractor.

Issued. 6-12-54

County Norton

KANSAS



CASING:

8 5/8" 247.01'

5 1/2" 3762.29'

Elevation. 2386 R B

Production. 182 BO/no wtr

Figures indicate Bottom of Formations.

shale	945
sand	1045
shale-sand	1615
sand	1735
red bed	1975
Anhydrite	2016
shale	2265
shale-lime	2510
shale-shells	2665
lime-shale	3701
shale	3715
lime-shale	3741
Total Depth	

TOPS:

Heobnor	3424
Toronto	3450
Lansong	3465
Boo Kansas City	3650
Arbuckle	3705
Roagan	3733
Pre. Cam.	3740.5

Perforated 6 holes 3707-09.
Filled up at rate of about
17 BPM, 90% oil. FOP and
potential taken 4/29/54 for 180
BOID from Arbuckle.

Cored this well and had following:

3701-05 Red shale

3705-33 Coarse xln glauconitic
sandy dolomite carrying fair to
good streaked porosity with good
show oil in all porous streaks to
3730.

3733-40 Fine to medium grain
dense to slightly porous sand,
carrying considerable black re-
sidual oil.

3740-41 Weathered pre cambrian
schist.