

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


25-3-24W

Company- WOOD RIVER OIL & REFINING CO., INC.
Farm- Cora Fought No. 6

SEC. 25 T. 3 R. 24W
SW SE SW

Total Depth. 3737'
Comm. 5-11-54 Comp. 5-21-54
Shot or Treated.
Contractor.
Issued. 7-24-54

County Norton
KANSAS



CASING:
8 5/8" 261' cem w/135 sx
5 1/2" 3737' cem w/100 sx

Elevation. 2407' DE

Production. 178 BO & no wtr.

Figures indicate Bottom of Formations.

surface hole	281
shale and shells	1993
anhydrite	2022
shale and shells	2795
shale and lime	3045
lime and shale	3215
shale and shells	3320
lime and shale	3460
lime	3635
lime and shale	3737 RTD
Total Depth	

Tops: Scout	
Kansas City	3459
Arbuckle	3717

DRILL STEM TESTS:

- #1 Top of Lans. KO. 3471 - 85' Rec. .5' rot. mud.
- #2 3720-3737' L-Packer failed to hold. no test.
- #3 3730-3737', Rec. 420' fluid, 150' of which was heavily oil cut mud and 270' of salt water 720# BHP
- #4 3700' with straddle packer, Rec. 300' of heavily oil cut mud -- no water.

Ran Lane Wells Gamma Ray-Neutron log & collar locator.

Perforated with 12 shots from 3728' to 3731' after which well swab tested 6 1/2 bbls. oil per hour off bottom -- no water.