

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


17-3-25W

Company- ANDERSON-PRICHARD OIL CORPORATION  
Farm- Brooks No. 1

SEC. 17 T. 3 R.25W  
SE SE SE

Total Depth. 3895  
Comm. 6-23-53 Comp. 7-4-53  
Shot or Treated.  
Contractor. Glenn W. Peel  
Issued. 8-1-53

County Norton  
KANSAS



CASING:  
8 5/8 205' cemented

Elevation 2481 DF

Production Dry

Figures Indicate Bottom of Formations.

surface clay	100
sand & shale	150
shale & shells	205
shale	1050
sand & shale	1460
shale & shells	1750
shale & red bed	2045
anhydrite	2080
shale & shells	2570
shale & lime streaks	2820
shale & shells	2935
lime	3490
lime & shale	3545
lime	3803
Arbuckle	3830
Arbuckle & lime	3875
lime & granite	3895
Total Depth	

TOPS:

Anhydrite	2045
Topeka	3308
Heebner	3428
Toronto	3458
Lansing	3468
Base KC	3666
Basal Penn. sand	3784
Arbuckle	3791
Reagan	3872
Granite	3882

DST #3: 3769-3803, open 30 min. weak  
blow for 4 min. SI 15 min. rec 10'  
mud, no shows, BHP 140#

DST #1: 3459-90, open 45 min. weak  
blow for 5 min. rec. 20' mud sl. OC  
at top, BHP 55#

DST #2: 3524-55, open 30 min SI 15 min.  
weak blow died immediately, rec 8'  
dr. mud w/ few oil specks, BHP 55#