

DRILL STEM TEST REPORT

Prepared For: **Murfin Drilling Co**

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

8 3S 26W Decatur KS

Hix # 1-8

Start Date: 2008.07.12 @ 04:44:32

End Date: 2008.07.12 @ 12:07:02

Job Ticket #: 32418 DST #: 1

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 07 2008

CONSERVATION DIVISION
WICHITA, KS

CONFIDENTIAL

NOV 05 2008

KCC

Trilobite Testing, Inc
PO Box 1733 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Murfin Drilling Co

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

Hix # 1-8

8 3S 26W Decatur KS

Job Ticket: 32418

DST#: 1

Test Start: 2008.07.12 @ 04:44:32

GENERAL INFORMATION:

Formation: **Tor- LKC "A-B"**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 06:13:32

Time Test Ended: 12:07:02

Test Type: Conventional Bottom Hole

Tester: Kyle Kinderknecht

Unit No: 31

Interval: **3449.00 ft (KB) To 3522.00 ft (KB) (TVD)**

Total Depth: 3522.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Fair

Reference Elevations: 2559.00 ft (KB)

2554.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 8369 Outside

Press@RunDepth: 154.08 psig @ 3453.00 ft (KB)

Start Date: 2008.07.12

End Date:

2008.07.12

Start Time: 04:44:37

End Time:

12:07:01


Capacity: 7000.00 psig

Last Calib.: 2008.07.12

Time On Btm: 2008.07.12 @ 06:11:32

Time Off Btm: 2008.07.12 @ 10:14:02

TEST COMMENT: IF 1/2 " Built to 7 3/4 "
FF Surface in 7 min built to 1/2 "



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1689.88	106.37	Initial Hydro-static
2	18.95	106.20	Open To Flow (1)
31	96.03	106.54	Shut-In(1)
91	680.64	106.97	End Shut-In(1)
92	101.47	106.78	Open To Flow (2)
152	154.08	107.41	Shut-In(2)
242	590.62	107.63	End Shut-In(2)
243	1677.18	107.87	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
15.00	HMCW 30%W 70%M	0.07
90.00	HWCW 60%W 40%M	0.44
90.00	HWCW 55%W 45%M	0.44
95.00	100%M	0.47

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Murfin Drilling Co

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

Hix # 1-8

8 3S 26W Decatur KS

Job Ticket: 32418

DST#: 1

Test Start: 2008.07.12 @ 04:44:32

Tool Information

Drill Pipe:	Length: 2882.00 ft	Diameter: 3.82 inches	Volume: 40.85 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length: ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 550.00 ft	Diameter: 2.25 inches	Volume: 2.70 bbl	Weight to Pull Loose:	93000.00 lb
		Total Volume:	43.55 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	6.00 ft			String Weight: Initial	80000.00 lb
Depth to Top Packer:	3449.00 ft			Final	81000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	73.00 ft				
Tool Length:	96.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3427.00	
Shut In Tool	5.00			3432.00	
Hydraulic tool	5.00			3437.00	
Safety Joint	3.00			3440.00	
Packer	4.00			3444.00	23.00 Bottom Of Top Packer
Packer	5.00			3449.00	
Stubb	1.00			3450.00	
Perforations	2.00			3452.00	
Change Over Sub	1.00			3453.00	
Recorder	0.00	8369	Outside	3453.00	
Recorder	0.00	6669	Inside	3453.00	
Blank Spacing	61.00			3514.00	
Change Over Sub	1.00			3515.00	
Perforations	4.00			3519.00	
Bullnose	3.00			3522.00	73.00 Bottom Packers & Anchor

Total Tool Length: 96.00

CONFIDENTIAL

NOV 05 2008

KCC



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Murfin Drilling Co

Hix # 1-8

250 N Water Ste 300
Wichita KS 67202

8 3S 26W Decatur KS

ATTN: Paul G

Job Ticket: 32418

DST#: 1

Test Start: 2008.07.12 @ 04:44:32

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity: 23000 ppm

Viscosity: 59.00 sec/qt

Cushion Volume:

bbl

Water Loss: 6.39 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 600.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
15.00	HMCW 30%W 70%M	0.074
90.00	HWCM 60%W 40%M	0.443
90.00	HWCM 55%W 45%M	0.443
95.00	100%M	0.467

Total Length: 290.00 ft

Total Volume: 1.427 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: RW .35 @ 60 deg

Serial #: 8369


Outside

8 3S 26W Decatur KS

Murfin Drilling Co

DST Test Number: 1

Pressure vs. Time




CONFIDENTIAL
NOV 05 2008
KCC

Ref. No: 32418

Trilobite Testing, Inc

Printed: 2008.07.15 @ 11:23:44 Page 5



DRILL STEM TEST REPORT

Prepared For: **Murfin Drilling Co**

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

8 3S 26W Decatur KS

Hix # 1-8

Start Date: 2008.07.12 @ 19:51:56

End Date: 2008.07.13 @ 03:20:56

Job Ticket #: 32419 DST #: 2

Trilobite Testing, Inc
PO Box 1733 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

CONFIDENTIAL
NOV 05 2008
KCC



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

Murfin Drilling Co

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

Hix # 1-8

8 3S 26W Decatur KS

Job Ticket: 32419

DST#: 2

Test Start: 2008.07.12 @ 19:51:56

GENERAL INFORMATION:

Formation: **LKC "D-G"**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 21:16:56

Time Test Ended: 03:20:56

Test Type: Conventional Bottom Hole

Tester: Kyle Kinderknecht

Unit No: 31

Interval: **3530.00 ft (KB) To 3585.00 ft (KB) (TVD)**

Total Depth: 3585.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Fair

Reference Elevations: 2559.00 ft (KB)

2554.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 8369

Outside

Press@RunDepth: 259.59 psig @ 3534.00 ft (KB)

Start Date: 2008.07.12

End Date:

2008.07.13

Start Time: 19:52:01

End Time:

03:20:55


Capacity: 7000.00 psig

Last Calib.: 2008.07.13

Time On Btm: 2008.07.12 @ 21:15:26

Time Off Btm: 2008.07.13 @ 01:17:26

TEST COMMENT: IF Surface building to BOB 23 min
FF Surface in 5 min building to 3 1/2 "



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1795.75	106.70	Initial Hydro-static
2	18.99	106.55	Open To Flow (1)
32	130.24	108.44	Shut-In(1)
91	1011.61	108.22	End Shut-In(1)
92	134.97	107.92	Open To Flow (2)
147	259.59	109.69	Shut-In(2)
241	988.66	109.06	End Shut-In(2)
242	1670.54	108.60	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
20.00	HVCM 50%W 50%M	0.10
105.00	Water 100%W	0.52
305.00	MCVScumO 90%W 10%M	1.50
90.00	OWCM 3%O 17%W 80%M	0.44

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

TOOL DIAGRAM

Murfin Drilling Co

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

Hix # 1-8

8 3S 26W Decatur KS

Job Ticket: 32419

DST#: 2

Test Start: 2008.07.12 @ 19:51:56

Tool Information


Drill Pipe:	Length: 2976.00 ft	Diameter: 3.82 inches	Volume: 42.19 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length: ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 550.00 ft	Diameter: 2.25 inches	Volume: 2.70 bbl	Weight to Pull Loose:	86000.00 lb
		Total Volume:	44.89 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	19.00 ft			String Weight: Initial	82000.00 lb
Depth to Top Packer:	3530.00 ft			Final	83000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	55.00 ft				
Tool Length:	78.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3508.00	
Shut In Tool	5.00			3513.00	
Hydraulic tool	5.00			3518.00	
Safety Joint	3.00			3521.00	
Packer	4.00			3525.00	23.00 Bottom Of Top Packer
Packer	5.00			3530.00	
Stubb	1.00			3531.00	
Perforations	2.00			3533.00	
Change Over Sub	1.00			3534.00	
Recorder	0.00	8369	Outside	3534.00	
Recorder	0.00	6669	Inside	3534.00	
Blank Spacing	32.00			3566.00	
Change Over Sub	1.00			3567.00	
Perforations	15.00			3582.00	
Bullnose	3.00			3585.00	55.00 Bottom Packers & Anchor

Total Tool Length: 78.00

CONFIDENTIAL
NOV 05 2008
KCC



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Murfin Drilling Co

Hix # 1-8

250 N Water Ste 300
Wichita KS 67202

8 3S 26W Decatur KS

Job Ticket: 32419

DST#: 2

ATTN: Paul G

Test Start: 2008.07.12 @ 19:51:56

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

70000 ppm

Viscosity: 59.00 sec/qt

Cushion Volume:

bbl

Water Loss: 6.38 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 600.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
20.00	HWCM 50%W 50%M	0.098
105.00	Water 100%W	0.516
305.00	MCWscumO 90%W 10%M	1.500
90.00	OWCM 3%O 17%W 80%M	0.443

Total Length: 520.00 ft

Total Volume:

2.557 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: RW .13 @ 60 deg

Pressure vs. Time




CONFIDENTIAL
NOV 05 2008

KCC

Ref. No: 32419

Printed: 2008.07.15 @ 11:24:04 Page 5

Trilobite Testing, Inc



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Murfin Drilling Co**

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

8 3S 26W Decatur KS

Hix # 1-8

Start Date: 2008.07.13 @ 13:22:05

End Date: 2008.07.13 @ 19:29:35

Job Ticket #: 32420 DST #: 3

CONFIDENTIAL

NOV 05 2008

KCC

Trilobite Testing, Inc

PO Box 1733 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Murfin Drilling Co

250 N Water Ste 300
Wichita KS 67202

ATTN: Paul G

Hix # 1-8

8 3S 26W Decatur KS

Job Ticket: 32420

DST#: 3

Test Start: 2008.07.13 @ 13:22:05

GENERAL INFORMATION:

Formation: LKC "H-K"

Deviated: No Whipstock ft (KB)

Time Tool Opened: 15:01:05

Time Test Ended: 19:29:35

Test Type: Conventional Bottom Hole

Tester: Kyle Kinderknecht

Unit No: 31

Interval: 3586.00 ft (KB) To 3670.00 ft (KB) (TVD)

Total Depth: 3670.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Fair

Reference Elevations: 2559.00 ft (KB)

2554.00 ft (CF)

KB to GR/CF: 5.00 ft

Serial #: 8369

Outside

Press@RunDepth: 57.59 psig @ 3590.00 ft (KB)

Start Date: 2008.07.13

End Date: 2008.07.13

Start Time: 13:22:10

End Time: 19:29:34

Capacity: 7000.00 psig


Last Calib.: 2008.07.13

Time On Btm: 2008.07.13 @ 15:00:05

Time Off Btm: 2008.07.13 @ 17:55:05

TEST COMMENT: IF Weak blow to 1" died back to 1/2"
FF Weak surface 10 30 min

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1764.00	107.58	Initial Hydro-static
1	18.52	106.79	Open To Flow (1)
32	148.06	108.02	Shut-In(1)
76	1025.64	108.07	End Shut-In(1)
77	54.33	107.81	Open To Flow(2)
105	57.59	107.87	Shut-In(2)
167	1018.21	108.35	End Shut-In(2)
175	1732.14	109.90	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
45.00	HWC60%W 40%M	0.22
45.00	Mud	0.22

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Murfin Drilling Co

Hix # 1-8

250 N Water Ste 300
Wichita KS 67202

8 3S 26W Decatur KS

Job Ticket: 32420

DST#: 3

ATTN: Paul G

Test Start: 2008.07.13 @ 13:22:05

Tool Information

Drill Pipe:	Length: 3039.00 ft	Diameter: 3.82 inches	Volume: 43.08 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length: ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 550.00 ft	Diameter: 2.25 inches	Volume: 2.70 bbl	Weight to Pull Loose:	130000.0 lb
		Total Volume:	45.78 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	26.00 ft			String Weight: Initial	83000.00 lb
Depth to Top Packer:	3586.00 ft			Final	83000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	84.00 ft				
Tool Length:	107.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		
Tool Comments:					

Tool Description

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3564.00	
Shut In Tool	5.00			3569.00	
Hydraulic tool	5.00			3574.00	
Safety Joint	3.00			3577.00	
Packer	4.00			3581.00	23.00 Bottom Of Top Packer
Packer	5.00			3586.00	
Stubb	1.00			3587.00	
Perforations	2.00			3589.00	
Change Over Sub	1.00			3590.00	
Recorder	0.00	8369	Outside	3590.00	
Recorder	0.00	6669	Inside	3590.00	
Blank Spacing	61.00			3651.00	
Change Over Sub	1.00			3652.00	
Perforations	15.00			3667.00	
Bullnose	3.00			3670.00	84.00 Bottom Packers & Anchor

Total Tool Length: 107.00

CONFIDENTIAL

NOV 05 2008

KCC



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Murfin Drilling Co

Hix # 1-8

250 N Water Ste 300
Wichita KS 67202

8 3S 26W Decatur KS

Job Ticket: 32420

DST#: 3

ATTN: Paul G

Test Start: 2008.07.13 @ 13:22:05

Mud and Cushion Information

Mud Type: Gel Chem

Mud Weight: 9.00 lb/gal

Viscosity: 58.00 sec/qt

Water Loss: 6.39 in³

Resistivity: ohm.m

Salinity: 1500.00 ppm

Filter Cake: inches

Cushion Type:

Cushion Length:

Cushion Volume:

Gas Cushion Type:

Gas Cushion Pressure:

ft

bbl

psig

Oil API:

Water Salinity:

deg API

ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
45.00	HVCM 60%W 40%M	0.221
45.00	Mud	0.221

Total Length: 90.00 ft

Total Volume: 0.442 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time



CONFIDENTIAL
NOV 0 5 2008
KCC