

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


21-3-27w

Company - A. J. STORMFELTZ
Farm - Brown No. 1

SEC. 21 T. 3 R. 27W
SE SW SW

Total Depth. 4075'
Comm. 8-20-48 Comp. 9-5-48
Shot or Treated.
Contractor. J. D. Ferrell Dlg. Co., Inc.
Issued. 10-2-48

County. Decatur
KANSAS



CASING:

8 5/8" 301' Cem w/150 Sx.

Elevation. 2599 ft.

Production. Dry

Figures indicate Bottom of Formations.

cellar	5
clay and sand	50
sand and shale	185
shale and shells	1150
shale and lime	1530
shale and sand	1615
shale and lime	1770
lime	1890
shale and shells	2200
anhydrite	2230
lime and shale	2585
lime	2675
shale and lime	2880
lime	2965
lime and shale	3000
lime, chalky	3055
lime and shale	3170
lime	3815
lime and shale	3925
shale and sand	3970
shale, sandy	3992
shale, sand & lime	4017
lime, Arbuckle	4075
total depth	

Tops:

Anhydrite	2200
Lansing	3544
Conglomerate	3972
Arbuckle	4016