

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-039-20452
6-3-28W

KANSAS DRILLERS LOG

S. 6 T. 3 R. 28 ^N/_W

API No. 15 — 039 — 20,452
County Number


Loc. C NE SE

County Decatur

Operator
George R. Jones

640 Acres
N

Address
Suite 1310, 125 N. Market Wichita, Kanas 67202



Well No. #1 Lease Name Robertson

Footage Location
660 feet from (N) ~~XX~~ line 660 feet from (E) ~~XX~~ line

Elev.: Gr. 2660'

Principal Contractor Abercrombie Drilling, Inc. Geologist Robert W. Hammond

Spud Date April 6, 1979 Total Depth 3900' P.B.T.D.

DF _____ KB 2668'

Date Completed April 11, 1979 Oil Purchaser D&A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/4"	8-5/8"	28#	329'	60-40 POZ mix	250	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator GEORGE R. JONES

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

D&A

Well No.

1

Lease Name

Robertson

S 6 T 3 R 28 EX W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Anhydrite	2355 (+313)
			Howard	3412 (-744)
			Topeka	3456 (-788)
			Heebner	3620 (-952)
			Br. Lime.	3657 (-989)
			Lansing	3665 (-997)
			"B" Zone	3690 (-1022)
			Bs. K.C.	3865 (-1197)
			L.T.D.	3903 (-1235)
<p>Set first plug @ 1300' w/70 sx; second plug @ 300' w/20 sx; third plug @ 40' w/solid bridge, w/10 sx; rat hole 5 sx; cemented 50-50 POZ, 6% gel. PD 11:45 p.m. 4/11/79</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

Operator

Title

April 19, 1979

Date

2-980

CONTRACTOR WELL LOG

OPERATOR: George Jones
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Robertson #1
 LOCATION: NE SE, Section 6-3S-28W
 Decatur County, Kansas
 SPUD DATE: April 06, 1979
 COMPLETION DATE: April 11, 1979

0	332	Surface soil, sand and shale
332	1303	Shale
1303	1925	Shale and sand
1925	2352	Shale
2352	2383	Anhydrite
2383	2625	Shale
2625	2863	Lime and shale
2863	3365	Shale and lime
3365	3595	Lime and shale
3595	3700	Shale and lime
3700	3715	Lime and shale
3715	3838	Shale and lime
3838	3900	Lime
	3900	Rotary Total Depth

Spud hole at 5:00 p.m., April 06, 1979. Drilled 332' of 12 1/4" hole. Ran 8 joints of used 28# casing. Set at 329' with 250 sacks of 60/40 posmix. Cement did circulate. Plug was down at 11:15 p.m., April 06, 1979.

T.D. 3900'. Set 1st plug at 1300' with 70 sacks, 2nd plug at 300' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 11:45 p.m., April 11, 1979.

SAMPLE TOPS:

Anhydrite 2352'
 B/Anhydrite 2383'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Robertson #1, NE SE, Section 6-3S-28W, Decatur County, Kansas.