

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

21-3-28W

Company. HALLIBURTON OIL PRODUCING
Farm. Harmon No. 3

SEC. 21 T. 3 R. 28W
C NW SE

Total Depth. 3980'

Comm. 1-22-64


Comp. 1-29-64

County Decatur
KANSAS

Shot or Treated.

Contractor. BURCH DRILG

Issued. 5-23-64



Elevation. 2747' KB

Production. 51 BOPD 45% Wtr

Figures Indicate Bottom of Formations.

shale & sand	2121
Base Anhydrite	2137
sand & red bed	2259
shale & red bed	2412
anhydrite	2446
lime & shale	3980 RTD
Total Depth	

TOPS: LOG

Cimarron anhydrite	2411
Howard limestone	3493
severy sand	3561
Base Severy Sand	3574
Topeka limestone	3587
Heebner shale	3701
Toronto limestone	3731
Lansing Kansas City	3744
Base Kansas City	3942

DST # 1 3754-3804. Op 1 hr. Weak blow
died in 10 min, of open flow period. Rec.
210' of oil cut mud. IBHP 1267# 30 min.;
IFP 13# to 52#; FFP 60# to 94#; FBHP
1226# 30 min.

DST # 2 3801-3827'. Op 1 hr. Weak blow.
died in 20 min of open flow period. Rec.
40' of mud and 135' of muddy salt water.
IBHP 1256# 30 min. IFP 13# to 32#; FFP
37# to 88#; FBHP 1201# 30 min.

DST #3 3838-3900. Op 1 hr. Weak blow
throughout test. Rec. 170' oil cut mud!
IBHP 1116# 30 min; IFP 12# to 33#; FFP
44# to 69#; FBHP 900# 30 min.