

State Geological Survey
WICHITA BRANCH
KANSAS DRILLERS LOG

15-039-20459
22-3-28W

API No. 15 — County — Number —

S. 22 T. 3S R. 28W ^{XX}_W

Loc. C SE NE

County Decatur

Operator

Vincent Oil Corporation

Address

230 O.W. Garvey Bldg., 200 W. Douglas, Wichita, KS 67202

Well No.

#1

Lease Name

Orr

Footage Location

660

feet from (N) (S) line

660

feet from (E) (W) line

Principal Contractor

John O. Farmer, Inc.

Geologist

Jim Reeves

Spud Date

7-25-79

Total Depth


3990'

P.B.T.D.

Date Completed

8-1-79

Oil Purchaser



Locate well correctly

Elev.: Gr. 2724'

DF 2727' KB 2729'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	28	244'	Common	170	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		Vincent Oil Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No.		Lease Name			
#1		Orr		Dry Hole	
S 22 T 3S R 28 W		- Decatur County, Kansas			
WELL LOG				SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.					
FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
Shale	-0-	325	LOG TOPS:		
Shale & Sand	325	2142	Anhydrite	2430 (+ 299)	
Gypsum	2142	2153	Severy	3592 (- 863)	
Sand	2153	2238	Topeka	3617 (- 888)	
Red Bed	2238	2430	Heebner	3732 (-1003)	
Anhydrite	2430	2463	Toronto	3764 (-1035)	
Shale & Shells	2463	2581	Lans.-K.C.	3776 (-1047)	
Shale & Lime	2581	3832	Bs. K.C.	3970 (-1241)	
Lime	3832	3990	Log T.D.	3992	
			Rotary T.D.	3990	
Lost Circ. @ 600 ft.					
Drill Stem Test #1 - 3788-3832 ft. 30-30-30-30 min. Weak blow increasing to fair. Recovered 50 ft. watery mud and 250 ft. salt water. IFP 31-104#, ISIP 1274# FFP 104-167#, FSIP 1261#					
Drill Stem Test #2 - 3830-3935 ft. Packer failure					
Drill Stem Test #3 - 3825-3935 ft. 45-45-45-45 min. Weak blow. Recovered 180 ft. mud with rainbow of oil. IFP 73-115#, ISIP 959# FFP 115-178#, FSIP 938#					
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.					
Date Received		 Signature John O. Farmer, Inc. President Title August 7, 1979 Date			

44-38861-250