

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

28-3-28W

COMPANY BURCH EXPLORATION, INC.

SEC. 28 T. 3 R. 28W
 LOC. C SE SE

FARM Vavroch

NO. 1

TOTAL DEPTH 3990

COMM. 3-21-67


COMP. 3-27-67

SHOT OR TREATED

CONTRACTOR Abercrombie Drlg.

ISSUED 4-22-67

COUNTY Decatur
 KANSAS



CASING

20 10
 15 8
 12 7" @ 265' w/125 SX
 13 5

ELEVATION 2747' DF

PRODUCTION DRY/LANS KC

FIGURES INDICATE BOTTOM OF FORMATIONS

0	120	Surface Clay
120	260	Sand
260	275	Shale
275	1260	Shells & Shale
1260	2050	Shale & Shells
2050	2080	Sand
2080	2440	Shale
2440	2473	Anhydrite
2473	2620	Shale
2620	3440	Lime & Shale
3440	3530	Shale & Lime
3530	3775	Lime & Shale
3775	3845	Lime & Shale with chert
3845	3990	Lime
	3990	Rotary Total Depth

Set 7-inch surface casing at 265 feet with 125 sacks of cement.

Dry and Abandoned.

FORMATION TOPS:

Anhydrite	2438	(+ 310)
Heebner	3730	(- 982)
Toronto	3762	(-1014)
Lansing	3777	(-1029)
T. D.	3990	(-1242)

ELEVATION:

	2748 K.B.
TOPS: SAMPLE	2747 D.F. (L&S)
Anhydrite 2440	2741 G.L.
Base Anhydrite 2473	

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Jack K. Wharton, do hereby certify that the above and foregoing is a true and correct copy of the log of the VAVROCH #1, C SE SE, Section 28-38-28W, Decatur County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.