

CONTRACTOR'S WELL LOG

32-3-28W

API#15-039-20,256

OPERATOR: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: TILDEN #1
 LOCATION: C NE/4 SE/4, Sec. 32-3S-28W
 Decatur County, Kansas
 Benny C. Singleton, Jr.
 SPUD DATE: January 16, 1973
 COMPLETION DATE: January 23, 1973

0	180	Clay & Sand
180	259	Shale
259	520	Shale & Shells
520	1660	Shale
1660	1880	Sand
1880	2141	Shale
2141	2225	Sand
2225	2418	Shale
2418	2450	Anhydrite
2450	2795	Shale
2795	3790	Lime & Shale
3790	3952	Lime
	3952	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 11 1974
 CONSERVATION DIVISION
 Wichita, Kansas

Drilled 259' of 12 1/4" surface hole, set 8-5/8" surface csg. at 258' K.B. w/175 sx. cement. Cement circulated. Plug was down at 9:45 p.m. 1-16-73.
 Dry and Abandoned

<u>SAMPLE TOPS</u>		<u>ELEVATION</u>
Anhydrite	2418 (+ 325)	2743 K.B.
B/Anhydrite	2450 (+ 293)	2742 D.F.
		2736 G.L.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)



Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the TILDEN #1, C NE/4 SE/4, Section 32-3S-28W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr,
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 25th day of January, 1973.

TOMLINSON OIL CO.

#1 TILDEN

32-3-28W
C NE SE

200 W. DOUGLAS WICHITA, KS.


CONTR ABERCROMBIE DRILLING

CTY DECATUR

GEOL BENNY SINGLETON

FIELD VAVROCH EXT

E 2743 KB CM 1/16/73 ^{CARD} ISSUED 1/25/73 IP D&A/BKC
1/23/73



API 15-039-20,256

SMP	TOPS	DEPTH	DATUM
ANHY		2418	+ 325
B ANHY		2450	+ 293
HFFB		3711	- 968
LANS		3756	-1013
BKC		3947	-1204
RTD		3952	-1209

8 5/8" 258/175SX

DST(1) 3762-3815/30-30-30-30, 1710' SW,
BHP 1246-1246#, FP 810-606# & 606-890#

DST(2) 3835-3880/30-30-60-30, 150' WM,
W/F SP OIL, BHP 837-766#, FP 36-71# & 71-107#

NO LOG