

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


33-3-284

Company- HALLIBURTON OIL & BURCH DRLG. CO.
Farm- Orr No. 1

SEC. 33 T. 3 R. 28W
C SW NW

Total Depth. 3960'
Comm. 4-19-61 Comp. 4-28-61
Shot or Treated.
Contractor. Burch Drlg.
Issued. 12-2-61

County Decatur
KANSAS



CASING:
8 5/8" 206' cem w/200 sx.

Elevation. 2732' KB

Production. Dry

Figures Indicate Bottom of Formations.

shale	2121
Anhydrite	2131
shale-red bed	2408
Anhydrite	2439
shale & lime strks	2855
lime & shale	3830
lime	3850
lime & shale	3960 RTD
Total Depth	

TOPS:

Anhydrite	2410
Howard	3497
Topeka	3589
Heebner	3704
Toronto	3735
Lansing	3751
Base Kansas City	3934

DST #1 3783-3793', op 1 hr, rec. 60' muddy
salt wtr. 310' salt water. IBHP 1295#/30
mins. IFP 55#, FFP 185#, FBHP 1235#/30 mins.

DST #2 3822-3830', op 1 hr, rec. 25' slightly
oil cut mud. IBHP 1195#/30 mins, IFP 20#,
FFP 20#, FBHP 1020#/30 mins.

DST #3 3857-3960', op 1 hr, rec. 20' mud.
IBHP 805#/30 mins, IFP 0#, FFP 0#, FBHP
705#/30 mins.