

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


33-3-28W

BURCH DRILLING CO., INC.
Company- HALLIBURTON OIL PROD. CO. &
Farm- Vavroch No. 3

SEC. 33 T. 3 R. 28W
C SW SE

Total Depth. 3942'
Comm. 8-1-60 Comp. 8-9-60
Shot or Treated.
Contractor. Burch Drlg.
Issued. 10-8-60

County Decatur
KANSAS



Elevation. 2728' RB

Production. Dry

CASING:
8 5/8" 217' cem w/175 sx.

Figures Indicate Bottom of Formations.

shale & shells	2000
Anhydrite (Blaine)	2030
red bed & shale	2402
Anhydrite	2433
lime & shale	3136
lime	3235
lime & shale	3600
lime	3942 RTD
Total Depth	

TOPS:

Blaine Anhydrite	2005
Anhydrite	2402
Topeka	3578
Heebner	3694
Toronto	3724
Lansing	3742

DRILL STEM TESTS:

#1 3702-30' op 30 mins., Rec. 8' mud.
IBHP 1295#/30 mins., IFP 0, FFP 0, FBHP
1175#/30 mins.

#2 3744-3800', op 1 hr., fair blow, died
in 20 mins., rec. 5' oil, 70' heavy oil
cut mud. IBHP 865#/30 mins., IFP 0,
FFP 0, FBHP 840#/30 mins.

#3 3812-35', op 1½ hrs., rec. 40' slightly
oil cut mud, 60' muddy salt water. IBHP
1280#/30 mins., IFP 40#, FFP 45#, FBHP
1205#/30 mins.

#4 3832-60', op 1 hr., rec. 5' very
slight oil cut mud. IBHP 160#/30 mins.
IFP 0#, FFP 0#, FBHP 55#/30 mins.