

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

33-3-28W

Company- HALLIBURTON OIL PROD. & BURCH DRLG. CO.
Farm- Vavroch No. 7

SEC. 33 T. 3
C SE SW

R-28W

Total Depth. 4247'

Comm. 9-13-61


Comp. 9-21-61

Shot or Treated.

Contractor. Burch Drlg.

Issued. 2-17-62

County Decatur
KANSAS



Elevation. 2727' KB

CASING:
8 5/8" 212' cem w/175 sx.
5 1/2" 3955' cem w/210 sx.

Production. 150 BOPD

Figures Indicate Bottom of Formations.

shale	1640
shale & sand	1990
shale	2374
Anhydrite	2417
lime & shale	3230
lime	3308
lime & shale	4105
lime & sand	4241 RTD
lime & sand	4247
Total Depth	

TOPS:

Blaine Anhydrite	2017
Cimarron Anhydrite	2374
Topeka (scout)	3556
Heebner	3667
Toronto	3695
Lansing	3710
Base Kansas City (scout)	3909
Conglomerate (scout)	4110
Arbuckle (scout)	4230

DST #1 4140-4148', op 1 hr, shut in 30 mins. Rec. 30' mud & 450' salt water. IBHP 1100#/30 mins. IFP 35#, FFP 220#, FBHP 1025#/30 mins.