

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


33-3-28W

BURCH DRILLING CO., INC. &  
Company- HALLIBURTON OIL PRODUCING CO.  
Farm- Vavroch No. 10

SEC. 33 T. 3 R. 28W  
C NW SW

Total Depth. 3946'  
Comm. 3-3-62 Comp. 3-12-62  
Shot or Treated.  
Contractor. Burch Drilling Co., Inc.  
Issued. 9-29-62

County Decatur  
KANSAS



Elevation. 2726' KB

Production. Dry

CASING:

3 5/8" 256' cem w/250 sx.

Figures indicate Bottom of Formations.

shale	2399
anhydrite	2432
shale	2532
shale & lime	2965
shale	3100
shale & lime	3825
lime	3877
shale & lime	3945 RTD
Shale & lime ?	3946
Total Depth	

TOPS: WELEX

Cimmaron Anhydrite	2399
Heebner	3694
Toronto	3723
Lansing	3740
Base Kansas City	3932

DST #1 3740-3795' op 65 min. Shut in 30 min. Rec. 3' oil, 143' oil cut mud, 100' slightly oil cut mud. IBHP 1038#/30 min. IFP 35#, FFP 123#, FBHP 763#/30 min.

DST #2 3787-3825' op 1 hr. Shut in 30 min. Rec. 2' oil, 33' oil cut mud. IBHP 845#/30 min. IFP 18#, FFP 35#, FBHP 523#/30 min.