

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


4-3-29W

Company- ANDERSON-PRICHARD OIL CORP.  
 Farm- Follnow No. 3

SEC. 4 T. 3 R. 29W  
 C S/2 NE SW

Total Depth. 3925'  
 Comm. 4-2-58 Comp. 4-11-58  
 Shot or Treated.  
 Contractor. Glenn W. Peel  
 Issued. 5-31-58

County Decatur  
 KANSAS



CASING:  
 8 5/8" 224' cem.  
 4 1/2" 3856' cem.

Elevation. 2691' RB

Production. P. 69 BO & .4 of 1%  
 BS/24 hrs.

Figures indicate Bottom of Formations.

shale	1125
shale & shells	1645
shale	2150
Anhydrite	2175
shale	2415
lime	2450
shale & shells	2530
shale	2710
lime	2835
lime & shale	3455
lime	3925 RTD
Total Depth	

TOPS:  
 Anhydrite 2150  
 Heebner 3653  
 Toronto 3683  
 Lansing 3696  
 Base Kansas City 3918

DST #1 3714-30, open 1 hr, SI 20 min, fair  
 blow thruout, rec. 120' gas, 48'  
 free oil & 20' HOCM, IFP 27#, FFP 45#,  
 BHP 305#.

Perforated 3719-23 w/4 jet shots per ft.  
 Az w/250 gal.