

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-3-29w

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Lotker No. 1

SEC. 4 T. 3 R. 29W
C NW SE

Total Depth. 3927'
Comm. 5-29-58 Comp. 6-6-58
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 9-6-58

County Decatur
KANSAS



Elevation. 2702' RB

Production. 33 BOPD

CASING:

8 5/8" 225' cem.
4 1/2" 3898' cem.

Figures indicate Bottom of Formations.

clay & shale	225
shale & shells	1715
shale	2160
lime	2175
shale	2425
Anhydrite	2460
shale	2550
shale & lime	3140
lime	3255
shale & lime	3705
lime	3742
lime & shale	3925
lime	3927
Total Depth	

TOPS:	SAMPLE	GAMMA RAY
Anhydrite	2160	
Heebner	3666	3667
Toronto	3695	3698
Lansing	3708	3707
Base Kansas City	3915	

DST #1 3727-42, ISI 20 min, op 1 hr, FSI 20 min. good blow thruout, rec. 75' free oil & 30' mud cut oil & 180' gas.
IBHP 750#, IFP 0, FFP 0, FBHP 300#.

Perf. 3737-3731 w/4 jet holes per ft.
Az w/250 BD acid.

Estimate well will pump 50 BOPD after load is recovered.