

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-3-29W

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Lotker No. 2

SEC. 4 T. 3 R. 29W
C SE NE

Total Depth. 3913'
Comm. 7-21-58 Comp. 7-28-58
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 9-13-58

County Decatur
KANSAS



CASING:
8 5/8" 226' cem.

Elevation. 2692' RB

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	1645
sand	1720
sand & shale	2020
shale	2155
Anhydrite	2170
shale	2430
hard lime	2445
Anhydrite	2555
red bed & shale	2620
shale	2845
shale & lime	3540
lime	3685
shale & lime	3727
lime	3750
lime & shale	3880
lime	3913 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Heebner	3652	3657
Toronto	3680	3690
Lansing	3694	3700
Base Kansas City	3906	3906

DST #1 3712-27, op 1 hr, SI 20 min, weak blow for 4 min., rec. 8' mud, IBHP 525#, FBHP 0#, FFP 0#, IFP 0#.

DST #2 3724-50, op 1/2 hr, weak blow for 4 min, SI 20 min, rec. 2' mud, pressures 0.