

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-3-29W

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Pollnow No. 1

SEC. 4 T. 3 R. 29W
NE NW SW

Total Depth. 4406
Comm. 3-19-53 Comp. 4-3-53
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 5-23-53

County Decatur
KANSAS



Elevation. 2701 DF

Production. 79 BOPD & NW

CASING:

8 5/8" 195' cem.
5 1/2" 3961' cem.

Figures Indicate Bottom of Formations.

surface clay & shale	198
shale	2100
anhydrite	2125
shale	2200
lime & shale	2650
shale	2800
lime	3075
lime & shale	3210
lime	3860
lime & shale	3905
lime	3950
shale & lime	4010
lime	4406
Total Depth	

Tops:	
Anhydrite	2425
Heebner	3668
Toronto	3698
Lansing	3710
Sandy Conglomerate	4096
Arbuckle	4188
Bonneterre	4244
Reagen Sand	4371
Granite	4397

DST: #1 3612-60', open 1 hr.
SI 20 min., rec. 75' mud
BHP 1140#.

DST: #2 3666-3726' open 1 hr.
strong blow, rec. 935' SW,
BHP 1230#.

DST: #3 3733-60', open 45 mins.
strong blow rec. 710' oil, 100'
HOCM, BHP 1050#.

DST: #4 3768-93' open 30 mins.
slight blow 3 min. rec. 7' mud.

BHP 0.
DST: #5 3806-62' open 1 hr.
weak blow, rec. 4' oil and 33'
HOCM, BHP 900#.

DST: #6 3872-3905' open 1 hr.
weak blow, rec. 60' OCM, BHP
165#.

DST: #7: 4086-4140', open 1 hr.
rec. 1530' muddy SW, BHP 1010#.

DST: #8: 4185-95' open 30 mins.
weak blow for 11 mins. rec. 9'
mud BHP 765#.