

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


4-3-39W

Company- ANDERSON-PRICHARD OIL CORPORATION  
Farm- Pollnow No. 2

SEC. 4 T. 3 R. 29W  
SW SW SW

Total Depth. 3941  
Comm. 5-2-55 Comp. 6-25-55  
Shot or Treated.  
Contractor. Suavage & Dunn Drilling Co., Inc.  
Issued. 8-20-55

County Decatur  
KANSAS



CASING:  
8 5/8 @ 202'

Elevation. 2099

Production. 105 BOPD

Figures indicate Bottom of Formations.

cellar	5
shale	1570
Dakota sand	1620
shale & shells	2100
shale & red bed	2450
anhydrite	2550
shale & shells	2885
lime & shale	3480
lime	3648
lime & shale	3750
lime	3848
shale & lime	3900
lime	3941
Total Depth	

TOPS:  
Heebner 3668  
Lansing 3710  
Base KC 3929

DST #1: 3732-50, open 1 hr. good blow thruout, rec. 840' gas, 670' free oil, IFP 25#, FFP 265#, BHP 555#

Core #1 3731-50 full rec.  
Core #2 3855-73 rec. 15'

MI & RUCT. Swbd. mud & CO @ top of plug @ 2913'. Ran Gamma Ray. Perf. w/ 7 sh. 3722-23, Perf w/ 4 sh. 3723-24, Packer @ 3650' BD form w/ water, injection rate 3 BPM, 1400# sqzd. w/ 150 sx cmt. Approx 90 sx cmt. into form. SP 3000#, Drld. cmt. & CO to 3915'. Perf. 3737-41½ w/ 8 SPF. Swbd. @ rate 6 BOPH, NW for 12 hrs.