

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


5-3-294

Company. ANDERSON-PRICHARD OIL CORPORATION  
Farm. Boettger No. 2

SEC. 5 T. 3 R. 29W  
SE SE SE

Total Depth. 3940  
Comm. 5-14-55 Comp. 6-27-55  
Shot or Treated.  
Contractor. Sauvage & Dunn Drilling Co., Inc.  
Issued. 8-20-55

County Decatur  
KANSAS



Elevation. 2707 RB

Production. 109 BOPD

CASING:

8 5/8 165'  
5 1/2 @ 3939'

Figures Indicate Bottom of Formations.

cellar	5
shale	872
shale & shells	2070
anhydrite	2100
shale & shells	2400
shale	2340
shale & red bed	2820
lime & shale	3130
lime	3180
shale & lime	3605
lime	3680
lime & shale	3745
lime	3810
shale & lime	3890
lime	3940
Total Depth	

TOPS:

Heebner	3171
Toronto	3702
Lansing	3711
Base KC	3934

DST #1: 3733-45, open 1 hr. SI 20 min.  
strong blow thruout, rec. 560' free  
oil, FFP 210#, BHP 580#.

Drld. cmt. & CO to 3905', Perf 3728-30  
w/ 9 HPF, Swbd. 8 1/2 BWP/6 hrs. Ran tbg.  
to sqz. Perf Packer set @ 3666' sqzd.  
perf 3728-30 w/ 146 sx cmt. MP 3000#  
Rev. out 15 sx drld. cmt. 3756' CO  
to 3905' Dry tstd 3 hrs. Hole dry.  
Perf. 3743-38 w/ 27 holes 1 hr. swb  
tst e.7 BO w/ tr. wtr. Swbd. 17 BO,  
NW/4 hrs. ran tbg & rods 12 hr pump  
tst 63 BO, NW