

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


5-3292

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Pollnow "B" No. 1

SEC. 5 T. 3 R. 29W
SW SW NE

Total Depth. 3928.
Comm. 12-11-52 Comp. 12-22-53
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 2-13-54

County Decatur
KANSAS



CAS:NG:
8 5/8" 201' cem.
5 1/2" 3919' cem.

Elevation. 2694 R.B.

Production. 145 Bbls. & no water
8 hr. test

Figures indicate Bottom. of Formations.

surface soils	202
shale	1320
shale and sand	1470
sand	1520
shale and sand	1550
shale	2410
anhydrite	2450
shale and shells	2560
shale	2875
lime	3030
shale	3260
shale and lime	3310
shale	3315
shale and lime	3480
shale	3600
shale and lime	3685
lime	3694
shale and lime	3713
lime	3920
lime	3928
Total Depth	

Tops:
Topeka 3474
Heebner 3647
Toronto 3678
Lansing 3689
R.T.D. 3920

DRILL STEM TESTS:

#1: 3682-94, op. 30 min., recov. 5' mud with oil specks, BHP 730#.

#2: 3708-23, op. 30 min., recov. 90' oil 60' muddy oil, BHP 1000#.

Set 5 1/2" @ 3919'. Ran tubing with Baker K cement retainer and squeezed perforations 3699-3701 with 250 sx. Max. press. 300#, reversed out 80 sx. Perforated 3719-25 with 8 shaped charges per ft. Swabbed 49 BO, no

water in 8 hrs. RT&R, POP. P 116 BO in 17 hrs. 12-54" SPM. P 145 BO in 24 hrs. 8 hr. state test: 145 BOPD, no water 12-54" SPM.