

6-3-29W

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey


S. 6 T. 3S R. 29 NE

Loc. NE, NE

API No. 15 - 039 - 2057 WICHITA BRANCH

County Decatur

640 Acres



Locate well correctly

Elev.: Gr. 2759'

DF 2763' KB 2764'

Operator Multistate Oil Properties c/o Tenneco Oil Company

Address Suite 139, Ciudad Bldg., 3000 United Founders Blvd. Oklahoma City, Oklahoma, 73112

Well No. 4-6 Lease Name Amanda

Footage Location 830' feet from (N) line 1207' feet from (E) line

Principal Contractor Abercrombie Geologist Mark Young

Spud Date 5-2-81 Date Completed 6-22-81 Total Depth 4030' P.B.T.D. 3968'

Directional Deviation Oil and/or Gas Purchaser Koch Oil Company

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24"	666.80	60/40 Poz Common	200 200	3% CC, 2% Gel 3% CC, 2% Gel
Production	7-7/8"	5-1/2"	15.50	4031	50/50 Poz Class A 60/40 Poz	50 175 425	2% CaCl ₂ 7-1/2# Gilsonite 2% Gel + Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD				4" Gun	3792-96
Size 2-7/8"	Setting depth 3941	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1st Stage - 300 Gal. MCA (15% MCA + 10% Acetic Acid + Clay Stabilizer + Inhibitor)	3792-96
2nd Stage - 800 Gal. Demulsion Acid	

INITIAL PRODUCTION

Date of first production 6-22-81 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS Oil 66 bbls. Gas 0 MCF Water 10 bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Sold Producing interval(s) (Pollnow) Lansing 3792-96

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Tenneco Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

4-6

Lease Name

Amanda

Oil

S 6 T 3S R 29 ^E/_W

NE, NE, 830' FNL, 1207' FEL

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	2503		GR	
Base	2535		CCL	
Severy	3587		CBL	
Topeka	3612			
Oread	3711			
Toronto	3760			
Lansing	3772			
BMC	3986			
RTD	4030			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Carolyn S. Arnold

Signature

Carolyn S. Arnold

Production Analyst

Title

July 14, 1981

Date

P-3-80M