

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

6-3-29W

COMPANY SOLAR OIL

SEC. 6 T. 3 R. 29W

FARM Amanda

NO. 2

LOC. SE SW NE

TOTAL DEPTH 3980'

COMM. 5-27-67

COMP. 6-5-67


SHOT OR TREATED

CONTRACTOR Red Tiger Drig.

ISSUED 7-22-67

COUNTY Decatur

KANSAS



CASING

20	10	
15	8 5/8" 228'	cem w/ 150 sx
12	6	
13	5 1/2" 3953'	cem w/ 100 sx

ELEVATION 2759' KB

PRODUCTION 77 BOPD 25% W/
GR 36/ Lans 3796 1/2 - 3800

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay & Shale	0	235
Shale	235	1355
Shale, Sand, Shale	1355	2085
Shale	2085	2500
Anhydrite	2500	2533
Shale & Lime	2533	2895
Shale	2895	3060
Shale & Lime	3060	3740
Lime	3740	3980

TOPS:

Anhydrite 2500
Heebner 3721'
Toronto 3755'
Lansing 3768'

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 6th day of June, 1967.

DRILL STEM TEST NO. 1 3778-3805

Tool open 2 hours - strong blow

Recovered 720 feet gas, 500 feet oil and 85 feet oil cut mud.

30 min. shut in test showed IBHP of 334# and final BHP of 317#

Initial flow 42# and Final flow of 201#

Co. _____