

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

6-3-29W

COMPANY SOLAR OIL


SEC. 6 T. 3 R. 29W

FARM Pollnow NO. 3

LOC. NE SE SE

TOTAL DEPTH 3980'
 COMM. 6-5-67 COMP. 6-11-67
 SHOT OR TREATED
 CONTRACTOR Red Tiger Drlg.
 ISSUED 7-15-67

COUNTY Decatur



CASING
 20 10
 15 8 5/8" 233' cem w/ 150 sx
 12 6
 13 5

ELEVATION 2729' KB

PRODUCTION Dry/ L KC

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	200	
Shale	200	2220	
Blain Anhydrite	2220	2237	<u>TOPS:</u>
Shale	2237	2480	
Anhydrite	2480	2513	Blaine Anhydrite 2220'
Shale & Lime	2513	2640	Cimmarron Anhy. 2480'
Shale	2640	3120	TOPEKA 3538'
Shale & Lime	3120	3635	HEEBNER 3712'
Lime	3635	3910	LANSING K.C. 3758'
Lime & Shale	3910	3980	

I certify that this is a true and correct copy of the above log' to the best of my knowledge.

TOPS: SMP
 Blaine 2220
 Base Blaine 2237
 Cimmarron Anhydrite 2480
 Base Cimmarron Anhydrite 2513
 Heebner 3712
 Lansing 3758

RED TIGER DRILLING COMPANY

Maxine V. Starr
 Maxine V. Starr

Subscribed and sworn to before me this 15th day of June, 1967.

Betty M. Maloney
 Notary Public

DRILL STEM TEST NO. 1 3772-3795
 Tool open 1 1/2 hours. Fair blow.
 Recovered 270 feet of muddy salt water with slight scum of oil
 30 min. ISIP - 318# 30 min. FSIP 276#
 IFP 21# FFP 131#