

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


8-3-29W

Company- SIERRA PETROLEUM CO., INC.  
Farm- Simpson No. 1

SEC. 8 T. 3 R. 29W  
NE NE SE

Total Depth. 3923'  
Comm. 5-4-56 Comp. 5-12-56  
Shot or Treated.  
Contractor.  
Issued. 6-9-56

County Decatur  
KANSAS



CASING:

8 5/8" 200' cem w/140 sx

Elevation. 2693' DF

Production. Dry

Figures indicate Bottom of Formations.

shale & sand	1580
shale and shells	1720
sand	1740
shale & sand	1810
sand	1850
lime & sand	1930
sand	1960
shale	2000
shale & shells	2075
anhydrite & shells	2100
shale & red bed	2160
anhydrite	2178
shale, red bed	2380
anhydrite	2425
shale & red bed	2600
shale & shells	2648
shale & red bed	2742
shale & lime	3714
lime	3792
lime & shale	3923
Total Depth	

Tops:	
Topeka	3514
Heebner	3667
Toronto	3696
Kansas City	3705
Base of Kansas City	3897