

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


9-3-296

Company- ANDERSON-PRICHARD OIL CORPORATION
Farm- Cochran No. 1

SEC. 9 T. 3 R.29W
NW NW NW

Total Depth. 3930
Comm. 11-7-55 Comp. 11-15-55
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 1-21-56

County Decatur
KANSAS



CASING:
8 5/8 194' cmtd.
5 1/2 3793' cmtd.

Elevation. 2699 RB

Production. 149 BOPD, NW

Figures indicate Bottom of Formations.

surface clay	60
sand	130
shale & shells	620
shale, shells & sand	1630
shale & shells	2430
anhydrite	2460
shale & shells	2850
shale & lime streaks	3040
shale & shells	3170
lime & shale	3290
lime	3370
shale & lime	3715
lime	3930
Total Depth	

TOPS:	
Heebner	3668
Toronto	3699
Lansing	3709

DST #1: 3731-42, Packer failed.

DST #2: 3730-42 dual packer, open 1 hr. SI 20 min. strong bl. thruout, rec. 370' gas, 50' oil, 180' HO&GCM, IFP 0#, FFP 110#, BHP 390#

CO to 3763 PGAC Meas. Ran Gamma Ray Neutron Log, Perf 8 SPF/3741-45, 3 hr blg. test 3/4 BO & 5% drlg. mud & wtr. 1000 gal acid under 50# press. time 15 min. Total load wtr. 115 bbls. Swbd. 72 BO, 69 BLW/10 hrs. Ran tbg & rods, 24 hrs pump test 162 BO, .4 of 1% wtr.