

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


9-3-29W

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Zander No. 1

SEC. 9 T. 3 R. 29W
C NW NE

Total Depth. 3920'
Comm. 1-28-59 Comp. 2-7-59
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 7-11-59

County Decatur
KANSAS



Elevation. 2686' RB

Production. Dry

CASING:

8 5/8" 224' cem.

4 1/2" 3775' cem.

Figures Indicate Bottom of Formations.

clay & shale	224
shale & shells	1910
sand	1920
shale & shells	2145
Anhydrite	2165
sand, shale & shells	2340
shale	2420
Anhydrite	2455
shale & lime	2460
lime, shells & shale	2680
shale & lime	3150
lime	3495
shale & lime	3600
lime	3715
Core	3738
lime	3920
Total Depth	

TOPS: SCHLUMBERGER

Blaine	2148
Base Blaine	2166
Anhydrite	2420
Heebner	3665
Toronto	3695
Lansing	3706
Pollnow Zone	3730
Base Kansas City	3910

DST #1 3722-38 Pkr failure

DST #2 3718-38', dual pkr. op 1 hr, no blow, rec. 210' mud. IBHP 110#, FBHP 0#, IFP 0#, FFP 0#, Tool had not worked properly.

Perf 3730-34', Az w/250 gal..Rainbow show.
Az w/4000 gal. Trace oil.
Perf 3695-3701', Az w/500 gal. no show.
Perf 3630-36, Az w/300 gal.
Did not recover load. P & A.