

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

23-3-29W


Company- W. W. SAUVAGE
Farm- Sauvage

No. 1

SEC. 23 T. 3 R. 29W
NE NE NE

Total Depth. 4337
Comm. 9-26-53 Comp. 10-6-53
Shot or Treated.
Contractor.
Issued. 12-12-53

County Decatur
KANSAS



CASING:
10" 165'

Elevation. 2675'

Production. Dry

Figures indicate Bottom of Formations.

plug & cement	165
shale & shells	1600
sand & shale	2050
shale & shells	2200
red rock & shale	2280
shale & shells	2375
shale & anhydrite	2580
shale & shells	2855
shale	3360
shale & lime	3415
shale	3520
shale & lime	3590
shale	3679
shale & lime	3752
lime	3790
shale & lime	4337
Total Depth	

SCOUT TOPS:

Anhydrite	2503
Lansing	3805
Base Kansas City	4010
Sandy Conglomerate	4233
Granite Wash	4269

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


23-3-29W

Company- W. W. SAUVAGE & DUNN DRLG.
Farm- Sauvage No. 1

SEC. 23 T. 3 R. 29W
NE NE SE

Total Depth. 4337'
Comm. 2-10-54 Comp. 2-20-54
Shot or Treated.
Contractor.
Issued. 8-9-58

County Decatur
KANSAS



CASING:
8 5/8" 165' cem.

Elevation. 2675' DF

Production. Dry

Figures Indicate Bottom of Formations.

DRILLERS LOG NOT AVAILABLE

- 3563-3571 finely crystalline & chalky
lime-some porosity-no show.
3633-3643 fine white limey micaceous
porous siltstone-no show.
3657-3666 same.
3759-3766 partly crystalline & vugular
lime-spotted slight porosity
no show.
3812-3827 oolitic lime-good porosity
water w/no show of oil.
3850-3856 partly crystalline, vugular,
& suboolitic lime-spotted
slight to fair porosity-small
show of heavy black tarry-oil-
fair odor.
3926-3932 trace vugular lime-very spotted
slight porosity-small show heavy
black tarry oil.
3955-3962 finely crystalline, partly vugular,
& chalky lime-spotted slight
porosity-spotted dark staining
no odor.

Total Depth 4337'

TOPS:

Cimarron Anhydrite	2503
Howard Lime	3555
Topeka Lime	3600
Heebner Shale	3769
Toronto Lime	3796
Lansing-Kansas City	3807
Base Kansas City & Top Marmaton Shale	4010
Sandy Conglomerate	4233
Granite Wash	4269

Meas. from top of RB.