

19-3-32W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

NATURAL OIL & GAS CO.
Company - ASHLAND REFINING CO.
Farm - W. O. Lewis "A" No. 1

SEC. 19 T. 3 R. 32W
SE SE SW

Total Depth. 4666
Comm. 11-10-53 Comp. 11-27-53
Shot or Treated.
Contractor. Natural Oil & Gas Co.
Issued. 12-19-53

County Rawlins
KANSAS



8 5/8 CASING; 220' w/ 250 sx cmt.

Elevation. 3066 RB

Production. Dry

Figures indicate Bottom of Formations.

clay, shale & sand	150
shale & shells	1600
shale & lime	1715
sand & shale	2325
sand	2370
shale & sand	2605
red bed & shale	2845
anhydrite	2858
red bed, shale & shells	3190
lime & shale	3700
shale	3780
lime & shale	4010
lime	4350
lime & shale	4519
shale, lime & sand	4552
shale & lime	4611
shale, sand & lime	4629
lime & chert	4666
Total Depth	

TOPS:	
Ft. Hays	1300
Codell	1365
Fairport	1500
Greenhorn	1600
Dakota	1715
Anhydrite	2823
Neva	3416
Admire	3544
Howard	3840
Topeka	3859
Heebner	4001
Toronto	4029
Lansing	4037
Base K C	4313
Marmaton	4323
Cherokee	4418
Mississippi	4622
Gilmore City	4640

DST #1: 3953-4000, open 1 hr. rec.
155' mud, BHP 260#

DST #2: 4032-54, open 1 1/2 hrs. rec.
1510' salt water. BHP 1240#

DST #3: 4213-52, open 1 hr. Wk blo
2 min. rec. 40' mud, BHP 160#