

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


18-3-35W

Company. EMPIRE DRILLING CO.
Farm- Beeson No. 1

SEC. 18 T. 3 R. 35W
C SW SW

Total Depth. 4890'
Comm. 8-31-62 Comp. 9-15-62
Shot or Treated.
Contractor.
Issued. 1-19-63

County Rawlins
KANSAS



CASING:

8 5/8" 309' cem w/150 sx.
5 1/2" 4768' cem w/150 sx.

Elevation. 3293' KB

Production. 249 BOPD, Tr. Wtr.

Figures Indicate Bottom of Formations.

surface shale 100
sand & shale 1915
shale 2215
shale & gyp 2425
sand stone & shale 2680
shale, shells w/gyp 2780
shale & shells 2920
shale, red bed 3080
Anhydrite 3127
shale 3355
lime & shale 3544
shale 3650
lime & shale 3750
lime 3802
lime & shale 4092
lime 4130
lime & shale 4220
lime 4282
lime & shale 4370
lime 4440
shale & lime 4660
lime 4671
lime & shale 4710
shale & hard sand 4755
sand & shale 4875
Mississippi 4890 RTD
Total Depth

Zone 6 4358
Zone 6A 4375
Zone 7 4404
Zone 8 4438
Base Kansas City 4473

TOPS: SCHLUMBERGER
Topeka 4017
Deer Creek 4058
Oread 4124
Heebner 4162
Douglas Sand 4177
Lansing 4209
Zone 2A 4262
Zone 5 4315