


28-2-36W

API# 15-153-20, 149

640 Acres  
N



Lease Name: Hubbard "A" Well No. 1  
 Well Located: 150' South NW SW  
Rawlins SEC 28 TWP 3S RGE 36W  
 Operator: Pickrell Drilling Company  
 Address: 705 Fourth National Bank Bldg., Wichita, Kansas  
 Elevation: Ground 3294 D.F. 3296 K.B. 3299  
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 2/23/ 19 73 Drilling Completed: 3/4/ 19 73  
 Well Completed: 19 Total Depth 4520'  
 Initial Production: \_\_\_\_\_

Casing Record

Size: 8-5/8" Set at 361' Size: \_\_\_\_\_ Set at \_\_\_\_\_  
 Size: \_\_\_\_\_ Set at \_\_\_\_\_ Size: \_\_\_\_\_ Set at \_\_\_\_\_

Liner Record

Size: \_\_\_\_\_ Set from \_\_\_\_\_ To \_\_\_\_\_

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8-5/8"</u>	<u>200</u>	<u>3/2</u>
_____	_____	_____
_____	_____	_____

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

Gamma, Neutron, Guard, Caliper (Great Guns)

(Fill in formation and related information on reverse side)

FORMATION, TESTING AND COMPLETION RECORD

Cont.

28-3-36w

Show Drill Stem Tests,  
Well Stimulation and  
Production Tests

Formation	Top	Bottom
Clay - Chalky Lime	0	170
Sand	170	250
Shale	250	2480
Shale & Sand	2480	2920
Shale	2920	3074
Anhydrite	3074	3115
Shale w/Lime Streaks	3115	3438
Shale & Lime	3438	3595
Lime & Shale	3595	3750
Shale & Lime	3750	3995
Lime & Shale	3995	4165
Lime	4165	4205
Lime Shale	4205	4305
Lime, RTD	4305	4520

DST # 1 3974-3996: Open 1 hour, weak blow 10 minutes  
rec. 3<sup>rd</sup> oil cut mud. FP's 10#-10#, ISIP 10#/30",  
FSIP 10#/30".

DST # 2, 4192-4206: Open 1 hr., weak blow 6 min. rec.  
5' mud w/oil spots. FP's 21#-21#, ISIP 38#/30",  
FSIP 21#/30".

DST # 3 4359-4409: Open 1 hr, weak blow 5 min. rec.  
5' mud. FP's 27#-27#, ISIP 31#/30", FSIP 27#/30".

DST # 4, 4446-4521: Open 1 hr., weak blow 10 mins.  
Rec. 10' mud. FP's 21#-21#, ISIP 26#/30", FSIP 21#/30"

