

DRILLER'S LOG

20-3-36W

MAR 19 1985

COMPANY: Coastal Oil & Gas Corporation

SEC. 20 T. 3S R. 36W

WELL NAME: Hubbard #1-20K

LOC. SW SE

COUNTY: Rawlins

RIG NO. #1

TOTAL DEPTH 4800'

ELEVATION

COMMENCED: 3-3-85

COMPLETED: 3-13-85

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 481' w/300 sx. common, 2% gel, 3% cc.

PRODUCTION: 5 1/2" @ 4795' w/225 sx. 60/40 poz., 2% gel, 10% salt, .75% CFR2 and 475 sx. Lite, 7# gilsonite.

LOG

(Figures Indicate Bottom of Formations)

Sand	436
Shale	490
Sand & Shale	850
Shale & Sand	2327
Sand & Shale	2884
Shale	2932
Shale & Sand	3193
Sand & Shale	3481
Shale	3721
Shale & Sand	4800
<u>ROTARY TOTAL DEPTH</u>	<u>4800</u>

APR 18 1985
State Geological Survey
WICHITA BRANCH

RECEIVED
STATE CORPORATION COMMISSION

APR 05 1985

CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF Kansas)
COUNTY OF Sedgwick)

SS: