

(Phillips farm)
Halmerick-Payne #1 Smith

Norton
36-3-23
SESENE
Elev-2350

An 1935 (71415) (driller) 10" 200'
(Rotary table brushing 2ft)
8AM 7/16 2265, 2/17 2595, 2775 lost and stuck 2/20 wash over

WEM T (3243) 3241 df - 891 (WEM)
Soft 3243-48 no show
Soft 3256-60 " "
Soft 3285-3301 " "
Very Soft 3322-60 - por ledge no show Core 3333 (1 in)
Soft 3469-75 no show Core 3373 1 in
Soft 3400-04 no show Core 3402 (1 1/2 in)

WEM ~~3400-11~~ ~~3458-60~~ 4048
Soft 3415-19 Core 3417 - no show
wh. traced lith. - some xln por - no stain
wh. lith. ls.

Heebner 3437 Douglas 3444
LKC 3461 (H) 3459 df - 1109
den buff cxln ls - sl. por - sl stain dead or
3461-63 (H) not soft - no odor (G-7)

Shale 3471-78 R & gn sh, R salt
KC Wgandell 3478 14 ft lith ls, th. col. not por

Soft 3510-13 Core 3512 (1 1/2 in) (3-3-4)
buff cxln, mud lit gray, trans. chit - sl xln por ls, v sl stain
no odor

Drum 3546 v. sl trace stan 3552-53

WEM Winterset 3578 3576 df - 1226

Bethany Falls 3614 vt. 3612 df - 1262

Core 3622 med soft (5-4-3 1/2) 3619-23 (Core 1 1/2 in) some por
with blk oil - some fairly thin but blk. much gilsonite
No odor or taste (leached subool, fos. many sm. fos)
Probably carried much water - Norton 3646

Best Show
Barbaric water?

Some stain 3650-52 (4-5) blk dead oil
Soft 3666-68 Core 3668 for blk oil no odor
no stain

red silt (Very soft 3668-72 (1-1-1) Core 3672 (1 1/2 in)
Soft por ls - mud thin blk oil - no odor or taste
Probably carrying those
Some red silt - probably dry set
Core 3668 3668 df
1316

