

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


18-4-18W

Company- SAM WALLINGFORD & WOODMAN & IANNITTI DRLG.SEC.
Farm- Bredemeier No. 1

18 T. 4 R. 18W
NW NW NE

Total Depth. 3500'
Comm. 12-4-61 Comp. 12-11-61
Shot or Treated.
Contractor. Woodman & Iannitti Drlg.
Issued. 5-5-62

County Phillips
KANSAS



CASING:
8 5/8" 162' cem w/130 sx.
5 1/2" 3330' cem w/85 sx.

Elevation. 1928' RB

Production. 20 BOPD

Figures Indicate Bottom of Formations.

clay	30
sand	40
clay	130
shale	630
sand & clay	1030
sand	1205
red bed	1210
red bed, shale & sand	1484
Anhydrite	1515
shale & shells	2075
lime	2665
lime & shale	2865
lime	3445
shale & sand	3476
Arbuckle dolomite	3500
Total Depth	

TOPS: SCOUT	
Anhydrite	1484
Heebner	3092
Toronto	3117
Lansing	3132
Conglomerate	3466
Arbuckle	3472