

NATIONAL ASSOCIATED PETROLEUM CO.

Office Memorandum

From John P. Deibel, Jr.

Date April 15, 1952

To Forrest H. Lindsay

Subject #1 Vera Emerick, NE SW NW

Sec. 10-4S-8W, Phillips Co., Kansas

Type: Wildcat

Elevation: 1894' D.F.

Total Depth: 3600' Driller; 3599' Schlumberger

Status: Dry and Abandoned

Dates: Spudded November 28, 1951; Under surface November 29, 1951;
Dry and abandoned December 12, 1951

Casing: Ran 217' of 8-5/8" surface casing set at 220', cemented
w/150 sacks;

Special Tests: Johnston Tester; Schlumberger Electric Log.

GEOLOGIC RECORD

<u>Formation</u>	<u>Sample</u>	<u>Schlumberger</u>	<u>Readings</u>
Topeka	2902	2903	
Heebner shale	3106	3106-11	
Lansing - Kansas City	3133	3136	
Zone 3 PSO		3196-3200	30/12/15
Zone 5		3237-39	22/32/8
Zone 7		3289-90	38/22/7
Base Kansas City		3374	
Arbuckle		3574-3600	

DESCRIPTION OF SPECIAL TESTS

DST #1 3055-3076; Open 1 hour, weak blow; Rec. 165' salty drilling fluid; BHP 900#

DST #2 3211-3226; Open 1 hour; weak blow 8 minutes; Rec. 5' heavy slightly oil cut mud; BHP 0

NATIONAL ASSOCIATED PETROLEUM CO.

Office Memorandum

om _____
Date April 15, 1952

Subject #1 Emerick, Phillips Co., Kansas

Continued from page 1

DST #3 3293-3316; Open 1 hour; weak blow 4 minutes;
Rec. 12' drilling fluid; BHP 0

DST #4 3583-3588; Open 1 hour; weak blow 7 minutes;
Rec. 25' drilling fluid; BHP 1050#

DST #5 3584-3600; Open 1 hour; strong blow;
Rec. 3000' slightly salty water; BHP 1100#

Yours very truly,

John P. Deibel, Jr.

John P. Deibel, Jr.

kc