

12-4-19W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- SOHIO PETROLEUM
Farm- Sophie Meyer No. 1

SEC. 12 T. 4 R. 19W
NW NE NE

Total Depth. 3621' PB 3374'
Comm. 4-4-54 Comp. 4-30-54
Shot or Treated.
Contractor. Bill Hay Drlg. Co.
Issued. 5-29-54

County Phillips
KANSAS



CASING:
8 5/8" 309' cem w/175 sx
5 1/2" 3409' cem w/125 sx

Elevation. 2001' RB

Production. 9 bbls in 9 hrs.

Figures Indicate Bottom of Formations.

surface clay, shale & sand	310
shale & sand	1552
Anhydrite	1583
shale & shells	1790
shale	1995
lime & shale	2290
shale & shells	2335
shale & lime	2595
shale & shells	2645
shale	2790
lime & shale	3175
lime	3490
lime & shale	3549
lime	3619½
lime	3621

Total Depth
Plugged back to 3374'

Tops: Scout
Lansing 3206
Base Kansas City 3429

Producing formation Lansing-Kansas City
from 3206-3429

DRILL STEM TESTS:

#1 3234-3254, open 60 min., recovered 1083'
of fluid, 411' oil, 662' gas, 10 MCO.

Acid treatment, 4-22-54 L-KC 1000 gallons.
Perforating Record 4-21-54, from 3246' to
3252', 24 shots. No shows. Odor in gun.
Swab test 104 & 8% wtr in 9 hrs or 9 bbls.